

SHIMOGA DIVISION.

Notification dated 22nd April 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 3 P.M. on 11th May 1940, for restoring Hetchi Thotadakere Reg. No. 1055, Sorab Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer on payment of annas four per form. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a treasury chellan for Rs. 240 credited to "17 (a) P. W. Deposits" in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Hetchi Thotadakere Reg. No. 1055, Sorab Taluk, in default of which tenders will be rejected."

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Chamundy Brand cement should be used for the work.

14. A reserve of 5 per cent on the value of work done will be withheld from the bills towards the security deposit.

Abstract of estimate for Restoring Hetchi Totadakere, Register No. 1053 of Sorab Taluk.

No.	Description of work	Unit	Rate	Quantity
	<i>Bund.</i> —TOP LEVEL OF BUND R.L. 56.00 AND WIDTH 6'		Rs. a. p.	
1	Clearing jungle and cutting grips, etc.	L. S.		
2	Earthwork to bund including watering and consolidation, etc., complete	C.yds.	0 6 0	4,099
3	Turfing the sides front and rear and watering, etc.	Sqrs.	0 10 0	315.00
4	Providing and fixing grade stones on concrete bed of 1'×1'×1' and figuring and painting, etc., complete	Each	2 8 0	39
5	Providing and fixing top width stones figuring and painting, etc., complete	"	1 0 0	39
6	Do do Register No. stones and date stone painting and figuring, etc., complete	"	6 0 0	1
7	Do do gauge stone do	"	25 0 0	1
8	Do do B.M. stones painting and figuring, etc., complete	"	5 0 0	2
	CONSTRUCTING C.I. PIPE 6" SLUICE No. 1.			
9	A high level sluice as per requirements of raiyats	L. S.		

No.	Description of work	Unit	Rate	Quantity
			Rs. a. p.	
	CONSTRUCTING SLUICE No. 2 SILL AT 46.50.			
10	Cutting open the bund to cill level and grips, etc., and refilling the same with watering and consolidation	L. S.		
11	Earthwork excavating foundation	C.yds.	0 4 0	8½
12	Laying cement concrete 1 : 3 : 6	C.ft.	0 8 0	136
13	Size stone in cement mortar 1 : 3	"	0 8 0	236
14	Burnt stone slabs dressed 6" thick	S.ft.	1 2 0	14
15	Providing teakwood plug with 1" steel rod with locking arrangement, etc., complete	L. S.		
16	Cement concrete slab 1 : 2 : 4 with plastering	C.ft.	1 2 0	17
17	Rough stone revetment in front and rear	L. S.		
18	Supplying and fixing 10" dia. cast iron pipe with Railway freight	R.ft.	5 0 0	48
19	Cutting orifice holes in slabs and unforeseen charges	L. S.		
	CONSTRUCTING SLUICE No. 3 SILL AT 47.00.			
20	Cutting open the bund to cill level with pipes, etc., and refilling with watering and consolidation	L. S.		
21	Earthwork excavating foundation	C.yds.	0 4 0	8
22	Laying cement concrete 1 : 3 : 6	C.ft.	0 8 0	133
23	Size stone in cement mortar 1 : 3	"	0 8 0	143
24	Burnt stone slabs 6" dressed	S.ft.	1 2 0	14
25	Cement concrete slabs 1 : 2 : 4 with ½" plastering	C.ft.	1 2 0	17
26	Providing teakwood plug with 1" steel rod and locking arrangement, etc., complete	L. S.		
27	Supplying and fixing 9" dia. C.I. pipe including Railway freight, etc., complete	R.ft.	5 0 0	36
28	Cutting orifice in slabs, etc., and unforeseen charges	L. S.		
29	Rough stone revetment in front and rear head walls, etc.	"		
	CONSTRUCTING SLUICE No. 4 CILL LEVEL AT 49.00.			
30	Cutting open the bund to cill level and refilling the same with watering and consolidation	L. S.		
31	Earthwork excavating foundation	C.yd.	0 4 0	7
32	Laying cement concrete 1 : 5 : 10 with ½" cement plaster	C.ft.	0 8 0	115
33	Size stone in cement mortar 1 : 4	"	0 8 0	171
34	Cement concrete slab 1 : 2 : 4 with ½" plastering	"	1 2 0	17
35	Burnt stone slab 6" thick dressed plug or upper orifice slab	S.ft.	1 2 0	14
36	Supplying and fixing 4" C.I. pipe including Railway freight	R.ft.	2 4 0	24
37	Do fixing teakwood plug with 1" steel rod and locking arrangement, etc., complete	L. S.		
38	Cutting orifices in slabs, etc.	"		
39	Rough stone work new in front rear head wall, etc.	"		
	CONSTRUCTING SLUICE No. 5 WITH CILL AT R.L. 49.00.			
40	Supplying and fixing 9" dia. C.I. pipe including Railway freight, joints, etc.	R.ft.	5 0 0	24
41	Excavating a contour draft sluice channel in laterite soil	C.yds.	1 0 0	274
42	Concrete in cement mortar 1 : 3 : 6 for masonry wings	C.ft.	0 12 0	34
43	Revetment work to approach and draft and other unforeseen works	L. S.		

No.	Description of work	Unit	Rate	Quantity
	CONSTRUCTING A WASTE WEIR (CREST AT 50.00).		Rs. a. p.	
44	Excavating foundation in hard laterite	C.yd.	1 0 0	10
45	Laying cement concrete 1:2:4 and with plastering $\frac{1}{2}$ " with cement	C.ft.	1 2 0	188
46	Grouting with cement concrete 1:5:10 the crevices in front of body wall, etc., and other unforeseen charges	L. S.	..	..
47	Clearing draft and approaches here and there	"	..	..
48	Rough stone revetments to waining banks, etc.	"	..	..

D. A. HUKERI,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

UNIVERSITY OF MYSORE.

COLLEGE OF ENGINEERING, BANGALORE.

Notification dated 23rd April 1940.

The following articles in the College of Engineering, Bangalore, will be sold by public auction on Saturday the 18th May 1940. The auction sale will commence at 8 A.M. and will be conducted in the College Workshop premises.

The terms and condition of auction sale will be as follows:—

(1) The articles will be knocked down to the highest bidder, and in the event of any dispute arising between two or more bidders at the same price, the articles shall be put up again and resold.

(2) The sale amount should be paid immediately. In case it could not be paid immediately, a deposit of 25 per cent of the amount should be recovered from the successful bidder immediately the articles are knocked down in his favour and such deposits shall be treated as forfeited to Government in case of any default to pay the full purchase money within 24 hours of the sale.

(3) Cash should be paid in full for articles purchased by bidders before delivery and the articles will not be allowed to be removed from the place of auction until after the close of the sale.

(4) In case of default of payment of the whole or any portion of the purchase amount by the bidder, the articles will be resold and the bidder will be liable to any loss incurred thereby. The bidder will be also liable to make good to Government any loss incurred thereby without having the right to participate in any excess realised.

(5) All articles purchased will be at the risk of the purchaser thereof from the time of sale.

(6) All articles should be accepted with faults and errors of all description as sold.

(7) The successful bidder must remove articles within 24 hours after his bid has been accepted.

(8) The officer conducting the sale may not accept the highest bid if the bid offered is not a reasonable value of the article.

List of unserviceable articles of the Engineering College and School to be auctioned.

Sl. No.	Description	Size	Number of articles	Sl. No.	Description	Size	Number of articles
1	Carpenters' Chisels	$\frac{1}{2}$ "	34	15	Blacksmith's Tongs	..	95
2	Do	$\frac{1}{2}$ "	20	16	Do Flatters	..	40
3	Do	$\frac{3}{8}$ "	7	17	Top and Bottom swages	..	10
4	Do	$\frac{1}{2}$ "	22	18	Do singles	..	23
5	Do	$\frac{1}{2}$ "	12	19	Set hammers and fullers	..	14
6	Do	1"	2	20	Claw hammer	..	1
7	Do	$1\frac{1}{2}$ "	9	21	Cocoonut, file and allied brushes.	..	23
8	Do	$1\frac{1}{2}$ "	104	22	G.I. Buckets	..	56
9	Blacksmiths' Chisels	..	26	23	Iron pans	..	77
10	Fitter do	..	218	24	C.I. Spirit levels	..	1
11	Ball-pane hammers	1 lb.	23	25	Foot-rule with spirit level	..	2
12	Do	$\frac{1}{2}$ lb.	4	26	Foundry shovels	..	4
13	Do	$1\frac{1}{2}$ & 2 lbs.	58	27	Pipe wrench	14"	1
14	Do	3 lbs.	1	28	Large pipe wrench	..	1